

Contractor Bid Sheet

FILL IN ALL HIGHLIGHTED AREAS AND DOUBLE CHECK YOUR MATH

Applicant/Homeowner: Raul Guajardo
Property Address: 2121 Jomar San Angelo, TX 76903

General Specifications and Requirements for all Amy Young Construction Contracts:

1. All products and materials shall be new in unopened containers and/or packaging.
2. The contractor shall clean construction debris from the dwelling and site to a dumpster or legal landfill at least once each week, and leave the property in broom clean condition. In occupied dwellings, debris shall be removed from living quarters daily.
3. Installation of all products and materials shall be according to the manufacturer's instructions.
4. "Install" means to purchase, deliver, set up, test and warrant a new component.
5. "Replace" means to remove and dispose of original material, purchase new material, deliver, install, test and warrant.
6. "Repair" means to return a building component to like new condition through replacement of parts, adjustment and recoating of parts.
7. "Reinstall" means to remove, clean, store and install a component.
8. Items identified as required for locally adopted housing standards (Housing Quality Standards, code or other applicable standard as detailed in Program Guidelines) must be performed/installed prior to final payment.
9. A detailed list of work items identified by location (i.e. North, South, East, or West sides) or room shall be included.
10. Contractor shall remedy any defect due to faulty material or workmanship and pay for all damage to other work resulting therefrom, which appear within one year from final payment. Further, contractor shall furnish owner with all manufacturers' and suppliers' written warranties covering items furnished under this contract prior to release of the final payment.
11. New materials shall be matched with existing materials so that patching work is consistent with surrounding surfaces.
12. All Change Orders must be approved by TDHCA prior to expense being incurred or work performed.
13. Any additional cost due to product or material upgrades is solely the contractor's expense unless authorized by the Contract Administrator and approved by TDHCA.
14. The contractor shall not enter into separate side agreements with the homeowner (or anyone else) to do additional work outside of the Work Write-up or in exchange for work on the Work Write-up.
15. Payment requests shall be based on satisfactory completion of individual or groups of spec items, verified by the Contract Administrator.
16. The contractor is responsible for, and shall verify all field dimensions, sizes, quantities, square footages, lineal footages, etc. before ordering materials, products or supplies. Quantities, square footages, linear footages, etc. listed on the Work Write-up are for the convenience of the contractor. THDCA and the Contract Administrator neither make nor imply any guarantee for the accuracy of these numbers.
17. All electrical work must meet the National Electrical Code adopted by the city or by the state for counties and be completed by a state licensed electrician.
18. All plumbing work must meet the International Plumbing Code adopted by the city or by the state for counties and be completed by a state licensed plumber.
19. On-site portable toilets and dumpsters (or other means of debris removal) shall be provided by the contractor.
20. If digging is required for building a ramp, the contractor is responsible for utilities located prior to breaking ground.
21. It is the Contractor's responsibility to comply with all applicable permitting requirements.
22. Contractor is responsible for ensuring that new work does not violate or encroach on property lines, setbacks or easements.